



## STEAMING AHEAD AT THE GEYSERS

On April 24, 2008, the Company announced that testing carried out by independent consultants GeothermEx, Inc. on well WGP-1 at the Western GeoPower Unit 1 project at The Geysers indicates that the well is a strong producer with an initial steam flow rate of 140,000 lb/hr (63,500 kg/hr) at a wellhead pressure of 137 psia, with a static reservoir pressure of at least 279 psia. Drilling of the well continues and flow testing will occur on completion of the well.

